


PLAN

NOTES:

1. PORTLAND CEMENT CONCRETE SHALL BE CLASS 4000.
2. ALL TRENCH BACKFILL SHALL BE CSTC OR CONTROLLED DENSITY FILL.
3. CONTROL DENSITY FILL SHALL MEET WSDOT STANDARDS AS STATED IN 2-09.3(1)E OR THE CURRENT VERSION OF THE STANDARDS AND SPECIFICATIONS FOR ROAD, BRIDGE AND MUNICIPAL CONSTRUCTION MANUAL M41-10.
4. ALL SAW CUTS SHALL BE VERTICAL AND IN STRAIGHT LINES AS DIRECTED BY ENGINEER.
5. TACK ASPHALT FACES OF SAW CUTS AND SEAL SAW CUTS WITH PG 64-22 OIL.
6. PAVING FABRIC (IF FOUND) WILL NOT REQUIRE REPLACEMENT.
7. THE CITY, AT ITS OWN DISCRETION, MAY REQUIRE REPLACEMENT OF FULL CONCRETE PANEL(S).



SECTION



RIGID PAVEMENT PATCHING AND RESTORATION DETAILS TRANSVERSE CUT

DRAWING NUMBER	ROW-2
SCALE	NONE
REVISION DATE	2/06
DEPARTMENT	TRANS